



RECEIVED  
MAY 21 2009

CITY OF SEATTLE  
HISTORIC PRESERVATION PROGRAM

The City of Seattle

## Landmarks Preservation Board

700 Fifth Avenue • Suite 1700 • Seattle, Washington 98124 • (206) 684-0228

### Landmark Nomination Application

**Name:** Franklin Apartments **Year Built:** 1918

**Historic Names:** Franklin Apartments

**Street and Number:** 2302 4<sup>th</sup> Avenue, 98121

**Assessor's File No.** 069600-0140

**Legal Description:** Lot 1, Block L, Bell's Fifth Addition to the city of Seattle, according to the plat thereof recorded in Volume 1 of Plats, page 191, in King County, Washington, less portion for street.

**Present Owner:** Howard A. Close  
2316 4<sup>th</sup> Avenue  
Seattle WA 98121

**Present Use:** Apartments **Original Use:** Apartments

**Original Owner:** Frank M. Jordan

**Architect:** George W. Lawton and Herman A. Moldenhour, associate architect

Administered by  
The Historic Preservation Program, Seattle Department of Neighborhoods

# TABLE OF CONTENTS

	<u>Page</u>
Building Description	1
Statement of Significance	
Neighborhood Context: The Development of Belltown	4
Apartment Development in Seattle	6
Building History	8
The Architects: Lawton and Moldenhour	9
The Georgian Revival Style	9
Terra Cotta in Seattle	9
Bibliography	10
Attachment A	
Vicinity Map	
Site Plan	
Attachment B	
Property Record Card	
Attachment C	
Current Photographs	
Attachment D	
Building Plans	

## BUILDING DESCRIPTION

### Setting

The Franklin Apartments are located on a 6,480 square foot lot on the northeast corner of 4<sup>th</sup> Avenue and Bell Street. This part of Belltown has a mix of older small-scale buildings and larger-scale new construction. The block to the north on 4<sup>th</sup> Avenue has primarily older small-scale buildings, including the Fleming Apartments and Two Bells Tavern. To the south is another 1920s apartment, the three-story Charlesgate. Across from this are two newer buildings, Security House (11 stories) and the Shelby Apartments. More high-rise buildings are located farther down 2<sup>nd</sup> Avenue in both directions and to the east on Bell Street.

### Exterior Description

The Franklin is a three story (plus daylight basement) building of mill construction with a gross square footage of 22,320 square feet. The building has a 60- foot frontage along 4<sup>th</sup> Avenue and 108 feet on Bell Street. Although it appears to be rectangular, a light well (approximately 55 feet wide and 15 feet deep) on the north side gives it a shallow U-shaped plan. The site slopes down slightly from west to east.

The Franklin's exterior uses terra cotta ornamentation to enhance what is basically a simple building. It has the general appearance of a large Georgian Revival townhouse with a prominent dentilled cornice and windows topped with splayed lintels. The primary (west) and south facades are faced with scored red brick, contrasting with the cream-colored terra cotta ornamentation. These facades have a three-part composition with prominent terra cotta courses above the basement windows and below the third story windows. The deep metal cornice has a row of small dentils. The cornice is of metal, with some paint flaked off. The tall parapet appears to be capped with dark-painted metal.

The arrangement of the west façade is symmetrical, with a center entry flanked by two bays, one with a single window and one with two windows. The entry bay has two windows on each floor. All the windows have original eight-over-one wood sash and terra cotta sills. The first and second story windows have splayed lintels with keystone lintels. The third floor windows have slightly simpler lintels and the basement windows have no lintels.

The entry has a wide terra cotta surround sitting on granite plinths. Above is a small wrought iron balcony sitting on a cornice supported by curved corbels with acanthus leaf bases. Below the cornice are a row of dentils and two urns of flowers. The outer vestibule has marble wainscoting, granite steps and a tile floor. The outer door is modern, but it retains the original leaded glass transom and sidelights. The inner vestibule has black-and-white marble wainscoting (perhaps from the original owner's own Alaskan quarry) and the original oak double doors with leaded glass sidelights.

The south elevation facing Bell Street has similar eight-over-one windows. Between each pair of windows are two smaller three-over-one kitchen windows. The parapet on this façade has the words “Franklin Apts.” painted in white in large block letters.

The rear (east) elevation on the alley is faced with red common brick; the face brick and the terra cotta water table wrap slightly around the corner. There is one bay of eight-over one windows at each side. In the center is a rear entry of wood with a multilight transom. Above this entry are two pairs of eight-over-one windows, flanked by smaller three-over-one windows. These are on the rear stairway and do not align with the stories. The upper window has a pulley evidently once used to move heavy objects into the building. This façade has a ghost sign with the building’s name.

### **Interior Description**

The Franklin has 36 units, averaging 500 square feet. This is the same number of units noted in the 1937 Tax Assessor’s report. It includes 36 studio units and eight one-bedroom apartments. The original plans mention several features indicating the high quality of the building, including oak floors in the main rooms and corridors, tile bathrooms, gas ranges, folding kitchen tables and closet beds. The kitchens had “cooling closets” with a space for a refrigerator, a new amenity that would not come into common use in apartments until the 1920s. The small lobby has a marble floor and wainscoting and leads to the main staircase. A secondary staircase is at the rear.

### **Building Alterations**

The Franklin has a very high degree of integrity and retains its original eight-over-one wood sash. No changes are apparent. The only recorded building permit (permit #548008) was in 1973, to improve corridor doors and enclose stairways to comply with new fire safety regulations.

## **STATEMENT OF SIGNIFICANCE**

The Franklin Apartments were designed in 1918 by prominent local architects George W. Lawton and Herman Moldenhour. It is a very good and intact example of the efficiency apartment building that became an important housing resource for downtown workers while adding richness and substance to the streetscape after the area was regraded. The three-story bay windows, decorative brickwork and terra cotta ornamentation add to the building’s distinctiveness.

### **Neighborhood Context: The Development of Belltown**

Belltown may have seen more dramatic changes than any other Seattle neighborhood, as most of its first incarnation was washed away in the early 20<sup>th</sup> century. The area now known as Belltown lies on the donation claim of William and Sarah Bell, who arrived with the Denny party at Alki Beach on November 13, 1851. The following year they established a claim north of the early settlement (Pioneer Square), on land largely covered with dense

cedar and fir forests. A steep cliff rose from the beach, where a Duwamish winter village was located at the foot of the future Bell Street. The Bell claim extended from Elliott Bay east to today's Yale Avenue North, from Pine Street north to Denny Way.

The Bells returned to California in 1856, after their cabin burned in the Battle of Seattle, a skirmish between the settlers and Native Americans. Bell returned in the 1860s to plat the property, but it was not until 1870 that he and his son Austin returned permanently. They then began to actively encourage commerce to spread northward, although the topography and poor roads made it a difficult task. Before his death in 1887, the elder Bell built a home and a hotel (both now gone) on 1<sup>st</sup> Avenue near Battery Street. In 1889 his son hired the architect, Elmer Fisher, to design a large residential building in the same block. Soon afterwards, Fisher designed an Odd Fellows Hall next door and a retail/hotel/office building (the Hull Building) across 1<sup>st</sup> Avenue. These substantial brick buildings, some distance from Pioneer Square, combined with the area's isolation to give Belltown a distinctive identity separate from that of downtown Seattle.

Also in 1889, the first streetcar service arrived in Belltown, extending from James Street to Denny Way along 2<sup>nd</sup> Avenue. The Front Street Cable Railway erected its elaborate powerhouse and car barn near Denny Way and 2<sup>nd</sup> Avenue in 1893. Within a few years, lines would run along Western and Elliott avenues to Ballard and on 1<sup>st</sup>, 2<sup>nd</sup> and 5<sup>th</sup> avenues to lower Queen Anne, with connections at Pike Street to Eastlake, Westlake and points north and east.

However, significant development on the Bell property was slowed by its isolating topography. A steep bluff rose from Elliott Bay to 2<sup>nd</sup> Avenue, then Denny Hill, too steep for horses to climb, extended between 2<sup>nd</sup> and 5<sup>th</sup> avenues north of Pine Street. With the economic growth following the 1897 discovery of gold in the Klondike, the business district expanded to the north, and many saw Denny Hill as a significant barrier to progress. City Engineer Reginald H. Thomson envisioned leveling the hill, using hydraulic jets to sluice the earth into Elliott Bay. In 1898, the first of three regrades in the vicinity occurred, lowering 1st Avenue between Pike Street and Denny Way by 17 feet. The area west of 1<sup>st</sup> Avenue was not regraded, and its steep slope kept it largely industrial.<sup>1</sup>

By 1910, Belltown was a thriving community of wood frame residences and small commercial buildings, with brick hotels for workers along 1<sup>st</sup> Avenue. The waterfront and the western slope bustled with wharves, the railroad, fish canneries, small manufacturers and livery stables. Small commercial buildings, brick workers' hotel and houses lined 1<sup>st</sup> and 2<sup>nd</sup> avenues. However, on June 10, 1910 a fire destroyed eight blocks on the western slope, from the waterfront to 2<sup>nd</sup> Avenue and Vine Street. The burned area was largely industrial, but with many small wooden cottages and workers' lodgings. Only one person

---

<sup>1</sup> Myra L. Phelps, *Public Works in Seattle: A Narrative History*, The Engineering Department 1875-1975, Seattle Engineering Department, 1975

died but hundreds lost their homes. The area was soon rebuilt with larger industries and new residences and apartments.<sup>2</sup>

The city's population continued to grow at a remarkable rate, nearly tripling to 237,194 by 1910. As the pressure for land increased, the city proceeded with regrading the remainder of Denny Hill. The second phase occurred between 1908 and 1911, when 27 blocks between 2<sup>nd</sup> and 5<sup>th</sup> avenues, from Pine to Cedar streets, were sluiced away. The greatest excavation was along Blanchard Street, which was lowered by 107 feet at 4<sup>th</sup> Avenue. This was the largest such operation in the world up to that time, moving six million cubic yards of dirt. The regrade opened up access to Belltown, Queen Anne and Lake Union, greatly enhancing property values. It was during this period, several years after the completion of the regrade, that the Franklin was built. The city regraded only the streets, with owners of individual lots required to hire their own contractors to level their property. Thus many pinnacles of land remained even into the 1920s. The embankment created along 5<sup>th</sup> Avenue remained for more than twenty years, until the third regrading phase.<sup>3</sup>

Everyone waited expectantly for the city to expand into the newly-cleared Regrade, but it remained filled with small commercial buildings and apartments. Perhaps the best known development in Belltown during this period was one that did not occur. In 1910 the Municipal Plans Commission hired Virgil Bogue to develop a comprehensive plan for the city. His plan, released in 1911, proposed a new civic center plaza and building complex at 4<sup>th</sup> Avenue and Blanchard Street, with broad boulevards radiating outwards. Voters rejected the ambitious plan, consolidating the city center downtown and forestalling any significant movement into Belltown for the next sixty years.

Belltown, like the rest of the city, evolved significantly during the 1920s. Its location close to downtown made it an ideal location for apartment buildings to house downtown and waterfront workers, with an accompanying array of cafes, taverns and small grocery stores. Belltown also became the center of the film industry in the Pacific Northwest. The numerous film exchanges and related suppliers made the vicinity of 2<sup>nd</sup> Avenue and Battery Street a mecca for theater owners and managers from Montana to Alaska. The automobile had become a significant feature of the city, and Belltown's close-in, low-density location encouraged auto-oriented businesses such as service garages. It also attracted light-industrial uses such as printers and small-scale suppliers and assemblers servicing downtown businesses.

The third and final regrading phase began in 1928 and was completed in December 1930. This phase extended from Fifth Avenue to Westlake Avenue, between Virginia and Harrison streets. In volume it was about two-thirds the size of the second phase, removing 4,233,000 cubic yards of dirt on a conveyor belt to barges on Elliott Bay.<sup>4</sup> However, the project was completed just as the country was entering a major depression. Population

<sup>2</sup> Clarence B. Bagley, *The History of Seattle from its Earliest Settlement to the Present Time*, Chicago: S.J. Clarke, 1916, pp. 514-515

<sup>3</sup> Phelps, pp. 18-20

<sup>4</sup> Phelps, pp. 32-33.

growth virtually came to a standstill and manufacturing stalled. The expected development in the newly-regraded area did not occur. For decades the area east of 5<sup>th</sup> Avenue contained primarily car dealerships, parking lots, motels and other low-density uses. Only recently has development come to this area.

Seattle was transformed perhaps more than any other large city by World War II. Its North Pacific location made it a strategic military location for the war against Japan. Its airplane factories, shipyards and steel mills made it a crucial part of the war effort. Boeing alone increased employment from 4,000 to 50,000 between 1939 and 1945. Belltown's apartments, workers' hotels and taverns boomed. The district's proximity to downtown and waterfront industry also made it a center for union activity, with the Seattle Labor Temple relocating to 1<sup>st</sup> Avenue in 1942. This trend continued through the 1950s, with numerous other union halls being constructed here.

However, growth was generally slow in the 1950s-60s, as the economy took some time to recover after the war. In 1953 the Battery Street Tunnel was completed from Aurora Avenue North to the foot of Battery Street, connecting the SR 99 highway through downtown. This new infrastructure, and the 1962 World's Fair just north of Belltown, led to the construction of several modern motels in the eastern part of Belltown. Otherwise, construction was primarily one- and two-story buildings at the eastern and northern edges.

### **Apartment Development in Seattle and Belltown**

Since its initial settlement, Belltown has provided affordable housing for workers. In the late-19<sup>th</sup> and early 20<sup>th</sup> century it was primarily cottages, rooming houses and hotels for industrial and maritime workers and their families. By the 1920s the neighborhood was one of the city's major centers for apartment development, providing modest but comfortable accommodations that were affordable for the sales clerks, clerical staff and other workers in downtown businesses.

Early Seattle residents had several multifamily living options, depending on their income and social level and family structure. A family who could not afford its own home might rent a duplex or triplex. Those who were in transition often moved into apartment hotels, which catered to the middle and upper classes by providing rooms and suites with bath facilities and meals served in central dining rooms. Single people who could not afford this option might live in a boarding house, with meals provided, or a rooming house, where residents relied on restaurant meals. A step up from the rooming house was the workers' hotel, which catered largely to single men (and some couples and families) with rooms without private bath or cooking facilities.

However, the city's growth in the early 20<sup>th</sup> century, and changing social and economic forces, soon made these choices inadequate. From the beginning of the Klondike gold rush in 1897 to 1910, Seattle's population increased 400%, from 55,000 to 237,000, and then to 315,312 in 1920. The city's role as a trade and manufacturing center solidified and downtown and neighborhood business districts boomed, with offices, stores and restaurants.

Streetcar lines spread throughout the city, allowing people to travel easily between neighborhoods.

This extremely rapid growth brought an acute need for housing, and builders and developers responded with a variety of housing types. The apartment block as it is known today, with a single primary entrance and living quarters, including kitchens, suitable for middle class residents, appears to have first been constructed in Seattle around the turn of the century. The first such building is believed to have been the St. Paul, constructed in 1901 on First Hill.

Between 1900 and 1910, land uses became more separated, with people of all income levels moving out of downtown. No regulations controlled the location of apartment buildings, but economics dictated that they were typically built on higher-value land close to downtown and near streetcar lines. Therefore, they generally appeared near neighborhood commercial areas and car lines in Belltown, Capitol Hill, First Hill, Queen Anne and the University District. Many of the commercial buildings on the main streets had apartments above first-floor businesses.

World War I and a subsequent recession slowed new development, leading to a pent-up demand for housing and very intensive development in the mid-to-late 1920s. By this time apartments were well established as a viable and acceptable housing option for the middle class, typically for single people or for those saving to buy a single-family home. With the economic prosperity of the 1920s, apartments often had amenities and luxuries that made them worthwhile alternatives to a single-family house. While this had been true to some extent in the preceding years, it became more common in the 1920s. The *Journal of Commerce* reported record amounts of construction in 1925, including "thousands of houses and scores of apartment houses." Multifamily development peaked in 1925 and continued strongly until 1930. The majority of the city's pre-World War II apartments were built during this period, with apartment blocks and mixed use buildings appearing along arterials in nearly every neighborhood.

A review of Baist maps and survey data shows that between the completion of the second Denny Regrade in 1911 and the Depression in 1930 at least 20 apartment buildings were constructed in the Belltown/Denny Regrade area. The most intensive apartment development occurred on 2<sup>nd</sup>, 3<sup>rd</sup> and 4<sup>th</sup> avenues. Belltown's future as an apartment district was confirmed in 1923, when Seattle adopted a comprehensive zoning ordinance. Those areas that already had apartment development were zoned for future apartments, while new apartments were prohibited in single family zones. Social conditions also encouraged apartment development, particularly the increasing role of women in the work force. Single women working in shops, offices and factories needed respectable and affordable housing, something that could not be obtained at the workers' hotels.

By the early 1920s, apartments were well established as an acceptable housing option for the middle class, typically for single people or for couples saving to buy a single-family home. Apartment features and sizes were targeted to the potential tenants that developers expected in a particular location. Because of Belltown's location close to downtown and



relatively distant from schools and playgrounds, its apartments were designed for downtown workers, either singles or couples without children. Thus, there were a large number of inexpensive efficiency units, or studios. Some buildings also had a variety of one-bedroom units, which would accommodate a couple, and even a few two-bedroom units, which could potentially accommodate a roommate or a child. However, Belltown does not appear to have had significant examples of the higher-end or luxury apartments built on First Hill and Capitol Hill during this period. These buildings (such as those developed by Frederick Anhalt) sought to provide all the amenities of an elegant home, including spacious apartments and landscaped surroundings, and Belltown was probably not considered sufficiently desirable as a neighborhood for this purpose.

Belltown, however, did have some of the city's best examples of two major types of apartment buildings. One is the single-purpose apartment building, with no commercial uses and a distinct front entrance and lobby, often quite elegant. The other type, found in most commercial areas throughout the city, is the mixed use building, with retail uses on the ground floor and one or more floors of apartments above. These typically have a more understated residential entry and a smaller lobby. Although some Belltown buildings have entry courtyards, the value of land meant that there are no courtyard or bungalow court apartments, with units arranged around a landscaped court.

Like the Franklin, the buildings usually had small lobbies, often clad with marble or other luxurious materials. Buildings up to three stories were unlikely to have elevators, so a central staircase ascended from the lobby area. Shared facilities such as laundry rooms and storage areas were in the basement. Apartments were usually arranged along double-loaded corridors with windows opening onto either the street or an inner courtyard or light well. The typical efficiency apartment was between 400 and 550 square feet in size and consisted of a living room, a full bath, and a kitchen with appliances and cabinets. Often a large closet or dressing room (which could contain the bed) opened off the living room. Wall beds and built-in cabinets and dinettes enhanced the usefulness of the small space. In many cases, leaded glass, oak floors and tile bathrooms added elegance. A one-bedroom unit would have most of the same characteristics, but with a separate bedroom rather than just the dressing room.

The Great Depression of the 1930s brought a precipitous drop in construction, especially as apartment financing disappeared. Apparently only one apartment building (the Grosvenor House/800 Wall Street, 1949) was built in Belltown between 1929 and the 1970s. By the 1960s many of the 1920s buildings had deteriorated and were in danger of demolition. The City of Seattle's Denny Regrade Development Plan of 1974 directly addressed the problem of providing new housing and preserving existing buildings. Zoning and building codes were changed to encourage housing and city and federal funding was used both to construct new buildings and to preserve the older apartment buildings that remain today.

## **Building History**

The Franklin Apartments were designed in 1918 by architects George W. Lawton and Herman Moldenhour for Frank M. Jordan. Jordan was president of F. M. Jordan & Company, a firm dealing in real estate, property rentals and loans. Jordan was born in Maine in 1863 and graduated from Williams College in 1887. He arrived in Seattle in 1889, about the time of the great fire. He saw the great opportunity presented by the rebuilding city, and immediately went into the real estate and insurance business. After the 1897 gold rush began, he developed properties in Alaska, including a copper and gold mine and a marble quarry. He later returned to Seattle and continued to develop and own properties.<sup>5</sup>

The length of Jordan's ownership is unclear, but L. A. Black purchased the building in 1932. During the 1940s, the building had numerous short-term owners, as did many apartment buildings. The current owner, Howard A. Close, the owner of the building next door and the Close Scientific Instrument Company, bought the Franklin in 1973.

### **The Architects: Lawton and Moldenhour**

---

<sup>5</sup> Clarence Bagley, *History of Seattle*, Seattle: 1916, v. 3: 495-496.

The Franklin is one of two Belltown apartment buildings designed in 1918 by George W. Lawton and Herman Moldenhour. The other one, the Castle Apartments (Photo C-12), has similar details but a considerably more complex façade composition. A few years later, in 1922, the architects cooperated again on the nearby Fifth Avenue Court (C-13). Their later apartment work (C-20) differs considerably from these earlier buildings. Olive Crest is a simple mixed use building on Capitol Hill, with ornate terra cotta ornamentation along the cornice line. Hawthorne Square, just south of Woodland Park Zoo, is a unique full-block townhouse development with understated ornamentation. They also completed ornate office buildings, including the Fourth and Pike Building (C-23), a Seattle landmark.

George W. Lawton was born in Wisconsin in 1863 and moved to Seattle in 1889, about the time of the Great Fire. He worked as a draftsman for the prominent firm of Saunders & Houghton before entering into partnership with Charles Saunders in 1898. The firm of Saunders and Lawton designed a wide range of projects. One of their specialties was apartments and hotels, including the Lincoln Apartment Hotel (burned), the San Marco (1905), and the Summit (1910). Another of the firm's specialties was warehouse structures, and they found a fertile market as the area around the train stations developed into a trade/distribution center. Some of their buildings in Pioneer Square are the Norton (1904), Mottman (1906), Goldsmith (1907) and Provident (1910) buildings. The firm also designed two of the city's oldest remaining schools, Horace Mann and Beacon Hill (now El Centro de la Raza) elementary schools. They adeptly used a wide range of revival styles, including Romanesque, Classical, Tudor and Colonial. One of their most noted works was the Forestry Building (1908-09) at the Alaska-Yukon-Pacific Exposition, a classical design executed in raw logs. Another well-known building is the Masonic Temple (1912-16, now the Egyptian Theater), completed by Lawton after the partnership dissolved in 1915. As an independent practitioner, Lawton worked with A. W. Gould on the Arctic Building (1913-17), famed for its terra cotta walrus heads.

In 1922 Lawton formed a partnership with Moldenhour (1880-1976), who had been an office boy for the Saunders & Lawton firm. One of their earliest joint projects was the Ravenna United Methodist Church. The firm specialized in large office and apartment buildings, including the Fourth and Pike Building (1927) and the Melbourne Tower (1927-28). The partnership ended with Lawton's death in 1928. Moldenhour continued with an independent practice, and was the supervising architect for the Port of Seattle's Sea-Tac Airport Administration Building in 1948. He died in 1976 at the age of 96.

### **The Georgian Revival Style**

The Franklin is a good example of the use of the Georgian Revival style, elements of which Lawton and Moldenhour and other architects of the period often used for apartment buildings. During the 1920s it was one of several Revival styles that became extremely popular for residences, which were made more impressive by its simple elegance. The use of the style for apartment buildings enhanced the impression of the apartments as both home-like and elegant.

As seen in local apartment buildings, the Georgian Revival is most often characterized by brick cladding, symmetrical facades, terra cotta lintels and sills, dentillated cornices and

double-hung windows (typically in a six- or eight-over-one configuration). Although all or most of these features are often seen in a Georgian Revival residence, apartment buildings typically have only a few of these characteristics. The major decorative feature is the entry, sometimes topped with a pediment (as in the Pittsburgh Apartments, Photo C-24) or a columned portico, as seen in the Algonquin and the Washington Arms (photos C-25, C-27).

### **Terra Cotta**

The Franklin is one of a number of Belltown/Denny Regrade buildings noted in Seattle's terra cotta survey conducted in the 1980s. Terra cotta is molded clay block that can be used either as cladding or as ornament. The plasticity of the clay and the manufacturing method allow it to be formed into extravagant shapes, which add variety and richness to the streetscape. Terra cotta ornament became very popular in the late 19<sup>th</sup>-early 20<sup>th</sup> centuries as the cost of cut stone grew prohibitive. This popularity coincided with Seattle's early commercial development, and the city has a particularly rich collection of terra cotta-clad buildings. The Seattle area had several prominent terra cotta manufacturers, including the Northern Clay Company and the Denny-Renton Clay & Coal Company. Both were acquired in 1925 by a California firm, the Gladding-McBean Company, making it one of the largest producers of terra cotta in the country.<sup>6</sup>

Seattle's best known examples of terra cotta are its early structural steel skyscrapers, beginning with the 1904 Alaska Building. Terra cotta lent itself to this use because it was much lighter in weight than stone or brick. However, the material was more widely used to clad or ornament smaller commercial buildings and apartment houses. In Seattle, terra cotta was typically glazed in cream or tan, sometimes with a mottled finish. However, any color was possible and some buildings featured colorful accents or terra cotta colored to look like granite (Granitex). Early 20<sup>th</sup> century terra cotta ornament typically used Classical, Gothic, Tudor or Mediterranean elements and motifs, but by the late 1920s Art Deco and Art Moderne terra cotta elements were more common. After World War II terra cotta use almost ceased, both because it was more costly than newer materials and because the modern architectural styles moved away from ornamentation of any kind. However, brightly colored terra cotta veneer was used on several Modernistic buildings, including the Seattle Labor Temple and the Sailors Union of the Pacific hall in Belltown.

### **Bibliography**

Aldredge, Lydia (ed.). *Impressions of Imagination: Terra Cotta Seattle*. Seattle: Allied Arts of Seattle, Inc., 1986.

Bagley, Clarence. *History of Seattle from the Earliest Settlement to the Present Time*. Chicago: S. J. Clarke, 1913.

---

<sup>6</sup> Lydia Aldredge (ed.). *Impressions of Imagination: Terra Cotta Seattle*. Seattle: Allied Arts of Seattle, Inc., 1986, p. 4.

\_\_\_\_\_. *History of King County*, Vol. II. Seattle: Pioneer Publishing Company, 1924.

*Baist's Real Estate Atlas: Surveys of Seattle, Washington*. Philadelphia: G. W. Baist, 1905, 1908.

Berner, Richard C. *Seattle 1900 - 1920: From Boomtown to Restoration*. Seattle: Charles Press, 1991.

\_\_\_\_\_. *Seattle 1921-1940: From Boom to Bust*. Seattle: Charles Press, 1992.

\_\_\_\_\_. *Seattle Transformed: World War II to Cold War*. Seattle: Charles Press, 1999.

Blanchard, Leslie. *The Street Railway Era in Seattle*. Forty Fort, PA: Harold E. Cox, 1968.

BOLA Architecture + Planning: Landmark Nomination for the Windham Apartment Building, Seattle, 2006.

Crowley, Walt, and The HistoryLink Staff. *Seattle & King County Timeline*. Seattle: History Ink and University of Washington Press, 2001.

Historylink.org, various essays on the Denny Regrade, <http://www.historylink.org>

King County Tax Division: Property Tax Records

<http://www5.metrokc.gov/parcelviewer/viewer/kingcounty/viewer.asp>.

King County Tax Assessor Property Record Cards. Washington State Archives, Puget Sound Branch.

Kroll Map Company Inc, Seattle, "Kroll Map of Seattle," 1912 - 1920, 1940 - 1964, and ca. 2000.

Lawton, George W., architectural plans, "Apartment House for Mr. William Carroll, 2-21-1922.

Museum of History and Industry, Digital Photo Collection, <http://www.seattlehistory.org/mohai>.


Nyberg, Folke and Victor Steinbrueck. *An Inventory of Buildings and Urban Design Resources*. Seattle: Historic Seattle, 1975.

Ochsner, Jeffrey, editor. *Shaping Seattle Architecture: A Guide to the Architects*. Seattle: University of Washington Press, 1998.

Phelps, Myra. *Public Works in Seattle: A Narrative History of the Engineering Department 1875-1975*. Seattle: Kingsport Press, 1978.

Polk, R. L., Company. *Seattle Directory*. 1889-1965.

*Sanborn Fire Insurance Maps of Seattle*, various years.



Franklin Apartments  
2100 4th Avenue



1" = 15'



**Photos C-24, C-25):** These are among the apartments with elements of the Georgian Revival style: Pittsburgh Apartments (117 John Street) and the Algonquin (1319 E. Union Street), designed by Graham and Myers.





Photos C-26, C-27: Other examples are the Lexington-Concord (2402 2<sup>nd</sup> Avenue) and the Washignton Arms (1065 E. Prospect Street).

